

JAIPUR DEVELOPMENT AUTHORITY, JAIPUR

No. JDA/EE-12B/2016/D-158

Dated 22/3/16

Corrigendum

NIB No. EE-12B/14/2015-16

Name of work:- Widening and Strengthening of road from Radha Swami Bag to Thana Mode, Chomu JDA Jaipur (Part-B Drain work).

उपरोक्त बिड की विक्रय तिथि, डाउनलोड/अपलोड तिथि एवं बिड खोलने की तिथियों में अपरिहार्य कारणों से निम्नानुसार संशोधन किया जाता है।

क्र.सं.	विवरण	पूर्व में प्रकाशित तिथि व समय	संशोधित तिथि व समय
1.	Start/End Date for Online Payment	Start Date : 24-02-16 at 09:30 AM onwards End Date : 24-03-16 at 06:00 PM	Start Date : 24-02-16 at 09:30 AM onwards End Date : 11-04-16 at 06:00 PM
2.	Start/End Date for Bid applying, Bid submission	Start Date : 24-02-16 at 09:30 AM onwards End Date : 24-03-16 at 06:00 PM	Start Date : 24-02-16 at 09:30 AM onwards End Date : 20-04-16 at 03:00 PM
3.	Date/Time/Place of Bid opening	31-03-16 at 03:30 PM CCC-TF-309, CCC Building, Ram Kishore Vyas Bhawan, Indira Circle, Jawahar Lal Nehru Marg, Jaipur-302004 (Rajasthan)	20-04-16 at 04:00 PM CCC, 1st Floor, CBFF-115, Ram Kishore Vyas Bhawan, Indira Circle, Jawahar Lal Nehru Marg, Jaipur-302004 (Rajasthan)

साथ ही Technical Bid की Special Condition के बिन्दु सं. 2 – Criteria for Potential Assessment एवं BOQ के आईटम नं. 1, 2 एवं 7 को निम्नानुसार पढा जावे।

क्र.सं.	पूर्व में प्रकाशित	संशोधित
2.	Non Pressure Pipes	Non Pressure Pipes size 300 mm & above
7.	Kerb Stone Laid by Kerb Laying Machine	Kerb Stone

BOQ		
क्र.सं.	पूर्व में प्रकाशित	संशोधित
1.	Earth work in excavation by mechanical means All kinds of soils	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sum on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with all lead. All kinds of soil.
2.	Providing and Laying Reinforced Cement Concre Providing and laying reinforced cement concrete	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106.
7.1	Excavation in Soil using Hydraulic Excavator and Excavation for roadwork in soil with hydraulic ex	Excavation in Soil using Hydraulic Excavator and Tippers with disposal upto 1000 m Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross-sections, and transporting to the embankment location with a lift upto 1.5 m and lead upto 1000 m as per MoRD Specification Clause 302.3.

निविदा की शेष शर्तें मूल निविदा के अनुसार यथावत रहेगी।


 अधिशाषी अभियंता जोन-12बी
 जविप्रा जयपुर